Repair Estimator

ddress: 407 Pine Ave, NN Date:

Bed: Bath: Sq Ft: Inspected By:

*** Additional Mediator/Engineer/Pro Quotes Needed:**

Asbestos	Buried Oil Tank	Fire D44amage		Foundation/Structural	Historical Home	Lead Paint	
Mold	Permit Check	Pool	Roof	Septic System	Sewer to Street	Soil	Well

EXTERIOR

Category	Y/N	Repair Type	#	Unit	Cost	Total
Roof * Possible additional Inspections, Quotes or Mediation needed		Roof (rip and replace) - architectural shingle	734	psf	$5.50	$4,037
		Rollover (add a layer of shingles) - architectural shingle		psf	$2.50	$0
		Roof Sheathing - plywood 1/2" remove & install		psf	$2.00	$0
		Roof repair/patch (hard)		ea	$900.00	$0
		Roof repair/patch (easy)		ea	$600.00	$0
		Premium for 3 layer tear off		psf	$0.35	$0
		Premium for steep pitched roof		psf	$0.20	$0
		Fascia - demo & install new		lf	$3.25	$0
		Soffit - demo & install new		lf	$2.00	$0
Gutters		Gutters & downspouts - demo & install new (Flat Cost)		sf	$4.00	$0
		Gutters & downspouts - demo & install new (linear foot)		lf	$6.00	$0
Finish		Demo existing finishing material		psf	$0.75	$0
		Stucco		psf	$3.00	$0
		Wood siding		psf	$5.00	$0
		Vinyl siding		psf	$3.00	$0
		Hardyboard		psf	$4.00	$0
		Plywood panel siding		psf	$2.50	$0
		Exterior Finishes for Bungalow - Columns, etc.		ls	$2,000.00	$0
		Power wash exterior finish		psf	$0.25	$0
Masonry		Fireplace/chimney, brick/stone - replace existing		ls	$5,000.00	$0
		Concrete block		sf	$6.00	$0
		Stone		sf	$18.00	$0
		Brick / Cutting out brick to put windows for lower level		sf	$11.50	$0
		Tuckpoint brick		sf	$3.50	$0
		Power wash exterior masonry		sf	$0.25	$0
Painting		Painting both exterior & interior (whole property)	734	psf	$3.50	$2,569
		Painting Ext only		psf	$1.60	$0
		Paint trim only		lf	$1.65	$0
		Sand & refinish deck or paint deck		sf	$1.75	$0
		Paint fence		sf	$1.00	$0
		Paint detached garage		sf	$1.00	$0
Windows		Windows, vinyl, average size		ea	$400.00	$0
		Windows, wood, restore existing wood (historical)		ea	$450.00	$0
		Window, large bay window - remove & replace		ea	$600.00	$0

EXTERIOR (cont.)

Category	Y/N	Repair Type	#	Unit	Cost	Total
Garage		Garage Door Only - 1 Car - 9'x7' door, manual		ea	$775.00	$0
		Garage Door Only - 2 Car - 16' door, manual		ea	$1,000.00	$0
		Garage Door Opener Installed		ea	$225.00	$0
		Reroof detached garage (rip & replace)		sf	$4.00	$0
		Build new detached garage		sf	$30.00	$0
Landscaping		Full landscaping makeover large lot (sod inc.)		ls	$5,000.00	$0

		Full landscaping makeover medium lot (sod inc.)		ls	$2,500.00	
		Full landscaping makeover small lot sod inc.)		ls	$1,500.00	$0
		Clean up landscaping & yard only	2	ls	$500.00	$1,000
		Tree removal (per tree)		ea	$500.00	
		Tree Planting (per tree)		ea	$130.00	$0
Concrete/Asphalt		Demo existing concrete or asphalt		sf	$2.00	$0
		Concrete installed for driveway/patio/sidewalk		sf	$5.00	$0
		Asphalt installed in driveway		sf	$3.00	$0
		Gravel installed for driveway/sidewalk		sf	$2.00	$0
Decks		New deck 15'x15' (add permit if 30" off ground)		ea	$9,000.00	$0
		Side Porch		ea	$5,000.00	$0
		New deck - treated lumber		sf	$15.00	$0
		New deck - cedar material		sf	$19.00	$0
		Decking material replacement only		sf	$7.00	$0
		Sand & refinish deck only		sf	$2.00	
		New railings - wood		lf	$20.00	$0
		New railings - metal		lf	$40.00	$0
Pergola		New pergola canopy 15'x15'		ea	$2,500.00	$0
		New pergola canopy 10'x10'		ea	$2,000.00	$0
Fence		Wood fencing		lf	$13.00	$0
		Wrought iron fencing		lf	$30.00	$0
		Chain-link fence		lf	$6.00	$0
Pool * Possible add'l Inspections needed		Pool Completely Redone ($10k to $15k)		ea	$10,000.00	$0
		Pool (redo plaster only)		ea	$4,500.00	$0
Septic * Possible additional Inspections, Quotes or Mediation needed		Septic (all new system)		ea	$15,000.00	$0
		Septic (new tank only)		ea	$6,000.00	$0
		Septic (replace leach field only)		ea	$4,000.00	$0

Exterior Notes

INTERIOR

Category	Y/N	Repair Type	#	Unit	Cost	Total
Painting		Interior painting only		sf	$1.50	$0
		Add extra wall prep (damaged walls)		sf	$0.50	$0
Hardwood		Hardwood flooring - solid wood		sf	$6.00	$0
		Engineered hardwood flooring		sf	$4.00	$0
		Laminate hardwood flooring	734	sf	$3.50	$2,569
		Sand & refinish existing hardwood flooring		sf	$3.00	$0
Carpet / Vinyl		Carpet		sf	$1.75	$0
		Vinyl or linoleum flooring		sf	$3.00	$0
Tiling		Ceramic floor tile - in kitchen		sf	$6.50	$0
		Backsplash wall tile - in kitchen		sf	$10.00	$0
		Ceramic floor tile - other areas of house		sf	$6.50	
Kitchen Includes: cabinets, counter-tops, backsplash, plumbing &		High end kitchen ($500+ ARV)		ea	$11,000.00	$0
		Median kitchen ($200-$500 ARV)		ea	$8,000.00	

tops, backsplash, plumbing & electrical work & fixtures in kitchen only. Excludes flooring, paint.		Low end kitchen (under $200ARV)	1	ea	$7,000.00	$7,000.00
		Low end kitchen - refinish existing cabinets		ea	$4,500.00	$0
		Kitchen extra custom items		ea	$500.00	$0
Kitchen - (By Item)		Cabinets		lf	$250.00	$0
		Countertops		sf	$45.00	$0
		Sink		ea	$300.00	$0
		Sink Faucet		ea	$150.00	$0
		Garbage Disposal		ea	$250.00	$0
		Refrigerator		ea	$1,000.00	$0
		Range		ea	$500.00	$0
		Range Hood		ea	$400.00	$0
		Dishwasher		ea	$500.00	$0
		Microwave		ea	$250.00	$0
Bathroom - (Grouped		Large master bath - replace everything		ea	$10,000.00	$0
Includes: vanity, counter-top, mirror, sink, faucet, tub, surround, shower-head & faucet kit, towel bar kit fan, lighting kit, basic plumbing & electrical work. Excludes flooring & paint		Full bath - replace everything	1	ea	$4,500.00	$4,500
		Half bath - replace everything		ea	$2,500.00	$0
		Add half bath		ea	$ 5,000.00	$0
Bathroom - (By Item)		Single Vanity cabinet		ea	$300.00	$0
		Double Vanity Cabinet		ea	$500.00	$0
		Vanity countertop - granite or other hard surface(2x for double)		ea	$150.00	$0
		Vanity mirror		ea	$75.00	$0
		Sink		ea	$125.00	$0
		Sink Faucet		ea	$150.00	$0
		Toilet		ea	$200.00	$0
		Bathtub - fiberglass		ea	$450.00	$0
		Glass Door		ea	$1,000.00	$0
		Bathtub & shower tile surround		ea	$700.00	$0
		Showerhead & faucet kit		ea	$210.00	$0
		Bathroom towel bar kit		ea	$75.00	$0

INTERIOR (cont.)

Category	Y/N	Repair Type	#	Unit	Cost	Total
Framing		New construction framing- (includes walls, floors & roof)		sf	$20.00	$0
		Replacing or sistering ceiling joist *Conservative		sf	$4.00	$0
		Installing Floor Beams in Basement		ea	$1,500.00	$0
		Subfloor put in (3/4" plywood)		sf	$2.50	$0
Insulation		Wall insulation		sf	$1.25	$0
		Floor insulation		sf	$1.25	$0
		Attic insulation, blown-in		sf	$0.80	$0
Walls		Drywall, tape & skimcoat walls/ceilings in gutted house		sf	$3.00	$0
		Drywall, tape, & skimcoat a wall (1/2" thick)	500	sf	$2.50	$1,250
		Skimcoating/texturing walls and ceilings only		sf	$1.00	$0
		Patchwork section of a wall - (drywall, tape, & finish)		ea	$500.00	$0
		Remove popcorn ceilings		sf	$1.00	$0
Doors & Trim		New interior doors, closet doors, hardware, & trim (3000 sq ft house)		ea	$3,000.00	$0
		New interior doors, closet doors, hardware, & trim (1500 sq ft house)	1	ea	$1,500.00	$1,500
		Interior door - prehung hollow-core door		ea	$150.00	$0
		Interior sliding closet door		ea	$150.00	$0
		Exterior front door - single door w/ hardware & dead bolt		ea	$300.00	$0
		Exterior french patio door - double door		ea	$700.00	$0
		Exterior sliding glass door - double door		ea	$850.00	$0
		Crown molding		lf	$3.75	$0
		New baseboard trim		lf	$2.00	$0
Foundation *		Foundation (Light - 5k Med - 10k Heavy - 15-30k)	1	lf	$6,000.00	$6,000

Interior Notes

MECHANICALS

Category	Y/N	Repair Type	#	Unit	Cost	Total
HVAC		Gas fired forced hot air heating system, ac system, & ductwork		ea	$10,000.00	$0
		Gas fired forced hot air heating system & ductwork		ea	$7,000.00	$0.00
		Gas fired forced hot air unit only		ea	$1,700.00	
		Air conditioning unit only		ea	$4,000.00	$0
		Replace forced air ductwork only		ea	$2,300.00	$0
		Replace boiler & hot water baseboard system		ea	$6,500.00	
		Replace boiler unit only		ea	$3,000.00	
		Wall heater (install new or remove & replace)		ea	$600.00	
		Service heating & cooling system only		ea	$500.00	
Plumbing		New plumbing system in entire house (1,500 sq. ft 3/2 house)		ea	$8,000.00	$0.00
		Replace tankless hot water heater		ea	$1,500.00	$0
		Replace gas hot water heater - 40 gallon		ea	$1,100.00	$0
Electrical		Rewire entire house, new panel, & lighting fixtures (1,500 sqft)		ea	$7,000.00	$0
		Basic electrical work for house & lighting fixtures (1500 sq. ft)		ea	$3,000.00	$0
		Lighting Updates		ea	$1,500.00	$0
		Replace all lighting fixtures only (1500 sq. ft. house)	1	ea	$1,000.00	$1,000

OTHER

Category	Y/N	Repair Type	#	Unit	Cost	Total
Demo & Dumpsters		Demolition work (cost to fill one 40 yd dumpster)		ea	$300.00	$0
		Dumpster rental (40 yard)		ea	$400.00	$0
Termites/Abatement Possible additional Inspections, Quotes or Mediation needed		Termite fumigation & treatment		ls	$1,000.00	$0
		Mold removal & abatement - minimum		ls	$3,000.00	$0
		Asbestos removal & abatement - minimum		ls	$4,500.00	$0
Extra **Note**: Anything that is not on the sheet already		Open up Wall (Small Wall Non-structural)		ea	$1,000.00	
		Exterior Front Porch Finishes		ea	$4,500.00	$0
		Plumbing Fittings		ea	$1,000.00	
		Fascia/Soffits (750sqft)		ea	$2,000.00	
						$0
					Repairs Subtotal	**$31,425**
Contingency		Misc Contingency Cost (10-20% depending on unknowns)	12	%	$31,425.00	$3,771
					Total Repairs	**$35,196**

SECTION TOTALS	
Exterior Repairs	$7,606
Interior Repairs	$22,819
Mechanical Repairs	$1,000
Other Repairs	$3,771

Total Repairs
$35,196